

**BOSE INSTITUTE
KOLKATA**

Tender No.	B.I./T/OVR/02/2017
Tender Date	30.01.2017
Tender Type	Limited

Tender Title	Miscellaneous work at Animal House, Madhyamgram Experimental Farm, Bose Institute.
Schedule of work	Annexure - II
Quantity	Please refer to Annexure - II

Last Date & Time for submission	09.02.2017 upto 2:00 p.m.
Date & Time for opening bids	09.02.2017 at 2:30 p.m.
Submission of Tender (address)	Tender box at Overseer Cell, (Room no 114) Main block ground floor at Centenary Building, Bose Institute, P-1/12, CIT Scheme VII-M, Kolkata 700 054
Venue of bid opening	Annexe Block, Centenary Building
For any query the interested bidders may contact (Dept./Section/Div./Unit)	033 2569 3212

General & Special Terms & Conditions	Annexure - I
Time of completion of the work	15 (Fifteen) days
Bid security (earnest money deposit) if applicable	N.A.
Any other information (if applicable)	N.A.

Name of the job and submission of tender should be mentioned on the envelope positively

Director, Bose Institute reserves the right to accept or reject any or all tenders either in part or in full. The reasons for rejecting the tender of a prospective bidder will be disclosed only when enquiries are made.

Sd/-
Sr. Professor & In-charge, Registrar's Office

BOSE INSTITUTE
P-1/12 C.I.T Scheme-VIIM
Kolkata - 700054.

NOTICE INVITING TENDER

Tender No.:- B.I./T/OVR/02/2017

Date: 30.01.2017

To

- | | |
|--|-------------------------|
| 1. M/s. Natural Resources Construction | 5. M/s. Sur Enterprise. |
| 2. M/s. Rita Construction. | 6. M/s. DPR Enterprise. |
| 3. M/s. Mani Construction. | 7. M/s. Colour Craft. |
| 4. M/s. Décor-in. | 8. M/s. Maa Enterprise. |

Name of Work: Miscellaneous work at Animal House, Madhyamgram Experimental Farm, Bose Institute.

Dear Sirs,

The undersigned invites you to tender your rates for works detailed in the enclosed schedule, subject to the following terms and conditions as integral parts of the contract for the tender.

1. Quotations in duplicate under a sealed cover superscripted with the words "Tender No. **B.I./T/OVR/02/2017** dated **30.01.2017** due on **09.02.2017** should be send to the office of the Registrar, at the above address, so as to reach **on or before 2.00 P.M on 09.02.2017 to be opened** at 2.30 P.M. on the same day.
- 1.a). The tenderers are requested to submit the photocopies of following documents duly signed by the proprietors / authorizes signatories along with the tender paper positively.
 - i) **Pan card of the owner**
 - ii) **Last Income Tax clearance certificate**
 - iii) **Valid Vat Registration certificate**
 - iv) **Proper authentication of proprietorship / Partnership/ Authorized representative of the Firm.**

Failing which the tenders may be treated as cancelled without showing any reason.

2. Tenders received beyond the schedule date and time will not be entertained in any case.
3. The tender/offer should be clear and precise quoting the net price(s) per unit both in words as well as figures, with break-up of different elements, if asked for. The price(s) quoted should be inclusive of Sales Tax, Income Tax, and other charges, etc.
4. In case the quotation is accepted and order placed, the contractor shall remain liable to complete the work within the stipulated date.
5. Time of completion **15 (fifteen) days from 3rd** day of receiving the Work Order.
6. Time, being the essence of contract, the contractor shall pay or allow the employer the sum equivalent to 1% of the total cost of work awarded per week, subject to a limit of 10% of the order value or the final bill amount whichever is greater, as liquidated damages for the period during which the said works shall remain incomplete beyond the time of completion mentioned above or beyond the time duly extended in writing. The employer may deduct such damages from any money due to the contractor.
7. Item prices once quoted will be firm and fixed. No price escalation will be entertained even for the works executed within the extended period, if any.
8. In case the order is cancelled due to non-compliance of the contractual terms and conditions, the Institute reserves the right to execute the job at its own cost and the differential amount, if any, on account of the alternative arrangement will be intimated to and recovered from him.
9. Guarantee period: The contractor shall give guarantee for a period of six months from the date of final handover and shall remain liable for rectification of defects, if any arises, within the said period at free of cost
10. All materials procured by the contractor will be subjected to inspection and/or tests prescribed in the specifications.
11. R/A or final bills: 90% payment will be made against your bill on actual measurement basis for the tender value worth of Rs. 20,000/- 100% payment will be released.
12. Incomplete tenders will be liable to cancellation.

13. The tender/offer shall remain valid for acceptance till 03 months from the scheduled date of its opening.
14. The contractor shall remain liable for any incidental charges occurred from natural calamities, accidents etc.
15. **Supplementary/Non-Schedule Items:** Rates for supplementary/Non-schedule items will be ascertained on the basis of P.W.D. Schedule of Rates, WBPCES (Current), plus/minus percentage above/below as reflected in contractor's quoted rates or the actual cost of materials and labour plus 15% towards overhead and profit, whichever is less.
16. **Water and Electricity:** Water and electricity as may be required for the work may be provided free of cost, subject to availability, at our source and contractor will make his own arrangement for distribution. However, no claim will be entertained for non-supply of water and electricity by the Institute.
17. **Storage Space:** A space for storage of materials may be provided by the Institute but the responsibility for security of the materials and machineries rests with the contractor.
18. **Removal of Rubbish/Debris:** The rubbish/debris etc. out of dismantling worn-out plaster, walls etc., shall be removed by the contractor from the work site from time to time, as per direction of the Engineer-in-charge.
19. **Indemnifying against damages:** Contractor shall, during the course of execution, be responsible for all damages to property and for any injury or loss caused to the work or workmen, to persons or things. The contractor shall make good all such damages besides damages out of dismantling plasters/walls/concrete surfaces during the course of execution at their own cost/risk.
20. **Work during holidays etc.:** Prior approval from the competent authority has to be obtained for persons to be engaged during holidays and/or beyond office hours, in listed form, mentioning, their names and addresses.
21. The quantities may vary up to 10% and beyond the limit of 10% approval of Competent Authority is required to be obtained prior to execution.
22. The contractor shall abide by the Rules and regulations of labour wages act.
23. Bose Institute reserves the right to reject any or all tenders without assigning any reasons thereof.

In case of any discrepancy, the order of precedence in interpretation shall as follows :

- (i) Schedule of Quantities and Rates.
- (ii) Special conditions of contract.
- (iii) Institute's General Conditions of contract.
- (iv) I.S. Code.
- (v) Best Engineering Practices.

Yours faithfully,

Sd/-
Sr. Prof & In – Charge
Registrar's Office

Enclosure: Schedule & Quantities

**Bose Institute
Kolkata**

Miscellaneous work at Animal House, Madhyamgram Experimental Farm at Bose Institute.

Sl, No	Description	Qty	Unit	Rate		Amount	
				Rs.	P	Rs.	P
1.	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters 30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	03	Sqm				
2.	Cement concrete flooring 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate	135	Sqm				
3.	Dismantling aluminum / Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable surplus material and stacking of serviceable material within 50 meters lead as directed by Engineer-in-charge.	40	Sqm				
4.	Providing and fixing tiled false ceiling of approved materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm centre to centre and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm centre to centre to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge 12.5 mm thick square edge PVC Laminated Gypsum Tile of size 595x595 mm, made of Gypsum plasterboard, manufactured from natural gypsum as per IS 2095 part I and laminated with white 0.16mm thick fire retardant PVC film on the face side and 12micron metalized polyester on the back side with all edges sealed with the face side PVC film which goes around and wraps the edges and is bonded to the edges and the back side metalized polyester film so as to make the tile a completely sealed unit.	35	Sqm				
5.	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)	3.5	Cum				
6.	20 mm cement plaster of mix 1:4 (1 cement: 4 coarse sand)	22	Sqm				

Total Rs